

Nr. Crt.	Capitolul de lucrari Simbol Denumire Resursa Observatii Corectii Liste Anexe	U/M	Cantitatea	Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d)	Materiale	Manopera	Utilaj	Transport	Total
5	ACD04H1 82	BUCATA	37,00000		0,000	0,000	0,000	0,000	0,000
CAMIN VIZITARE STAS 2448-73, ADANCIME MEDIE 2,5 METRI									
6	ACD01G1 82	BUCATA	37,00000		0,000	0,000	0,000	0,000	0,000
CAPAC SI RAMA STAS 2308-81 PENTRU CAMINE CU PIESA SUPORT NECAROSABIL TIP I \$									
7	ACE02A1 82	BUCATA	40,00000		0,000	0,000	0,000	0,000	0,000
GURA SCURGERE APE PLUVIALE, CAROSABILA, CLASA E600, DIAMETRU DE RACORD 160MM									
8	ACD01J1 82	BUCATA	40,00000		0,000	0,000	0,000	0,000	0,000
CAPAC SI RAMA STAS 2308-81 PENTRU CAMINE CU PIESA SUPORT CAROSABIL TIP III A \$									
9	00609Q11 02	BUCATA	10,00000		0,000	0,000	0,000	0,000	0,000
RIGOLA CU BRETEA CAROSABILA L =1000MM, L =200MM, H REDUSA									
10	01204B1 02	BUCATA	5,00000		0,000	0,000	0,000	0,000	0,000
CAMIN COLECTOR RIGOLA CU GRATAR CAROSABIL =500MM, L =200MM, H= 800MM CU IESIRE ORIZ.									

Nr. Crt.	Capitolul de lucrari Simbol Denumire Resursa Observatii Corectii Liste Anexe	U/M	Cantitatea	Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d)	Materiale	Manopera	Utilaj	Transport	Total
									0,000
11	TSC02D1 82	SUTE MC	8,96000		0,000	0,000			
	SAPATURA CU EXCAVAT.PE PNEURI 0,21-0,39 MC PAMINT UMIDIT.NATUR DESC AUT.TER.CAT.2						0,000	0,000	
									0,000
12	TSF06A1 82	MP	300,00000		0,000	0,000			
	SPRIJ.MAL.CU DULAPI MET.ASEZ.ORIZ.,LAT.INTRE MAL.1,51-2,5M,LA ADINC.SUB 4M;0,0-0,2M INTRE DULAPI						0,000		
								0,000	0,000
13	ACE08A1 82	M CUB	179,00000		0,000	0,000			
	UMPLUTURA IN SANT.LA COND.DE ALIM.CU APA SI CANALIZARE CU: NISIP \$						0,000		
								0,000	0,000
14	TSD04B1 82	M CUB	896,00000		0,000	0,000			
	COMPACTAREA CU MAI.DE MINA A UMPLUT.EXECUT.PE STRAT.CU UDAREA FIEC.STRAT DE 10CM GROS.T.COEZIV						0,000		
								0,000	0,000
15	TSA24A1 82	ORE	100,00000		0,000	0,000			
	EPUIZAREA MEC.A APEI DIN SAP.IN TEREN CU INFILTR.PUTERNICE CU MOTOPOMPA DE APA DE 6,6-12KW						0,000		
								0,000	0,000
16	TRA02A30 82	TONE	2.350,00000		0,000	0,000			
	TRANSPORTUL RUTIER AL MATERIALELOR CU AUTOCAMIONUL PE DIST.=						0,000		
								0,000	0,000

Nr. Crt.	Capitolul de lucrari Simbol Denumire Resursa Observatii Corectii Liste Anexe	U/M	Cantitatea	Pretul unitar a) materiale b) manopera c) utilaj d) transport Total(a+b+c+d)	Materiale	Manopera	Utilaj	Transport	Total
30 KM.	\$							0,000	0,000
17	TRB05B25 82	TONE	2,00000		0,000	0,000			
TRANSPORT PRIN PURTARE DIRECTA PE DISTANTA DE 50M(TEAVA, ROBINETI, IZOLATII CONDUCTE)									0,000
18	SF05C1 82	M	996,00000		0,000	0,000			
EFECTUAREA PROBEI DE ETANS.LA PRES.SI SPALAT COND.DE APA,DIN TUB FONTA PRES									0,000
Cheltuieli directe					0,000	0,000	0,000	0,000	0,000
Alte cheltuieli directe									
Contrib. Asig. Munca				2,250%		0,000			0,000
TOTAL CHELT. DIRECTE					0,000	0,000	0,000	0,000	0,000
Cheltuieli indirecte			Io =	0,000% x To					0,000
Profit			Po =	0,000% x (To+Io)					0,000
TOTAL GENERAL categoric			Vo =	To+Io+Po					0,000

PROIECTANT
SC INGVISION SRL

